

BID FORM

**KING ROAD (T-100)**  
**ROADWAY IMPROVEMENTS**  
**SR 25 TO HULL PRAIRIE ROAD**  
**MIDDLETON TOWNSHIP, WOOD COUNTY OHIO**

REF. NO.	ODOT ITEM	ESTIMATED QUANTITY	UNIT	ITEM DESCRIPTION	UNIT PRICE	TOTAL BID
<b>ROADWAY</b>						
1	201	LUMP	CY	CLEARING AND GRUBBING		
2	202	11.5	SF	WALK REMOVED		
3	202	91	SY	PAVEMENT REMOVED		
4	202	30	LF	PIPE REMOVED		
5	203	530	CY	EXCAVATION		
6	203	1435	CY	EMBANKMENT		
7	204	4158	SY	SUBGRADE COMPACTION		
8	411	367	CY	STABILIZED CRUSHED AGGREGATE		
9	452	91	SY	NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1		
10	659	4879	SY	SEEDING AND MULCHING		
11	659	0.42	TON	COMMERCIAL FERTILIZER		
<b>PAVEMENT</b>						
12	254	323	SY	PAVEMENT PLANING, ASPHALT CONCRETE		
13	301	694	CY	ASPHALT CONCRETE BASE		
14	407	1700	GAL	NON TRACKING TACK COAT, (0.08 GAL/SY)		
14	441	831	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448)		
15	441	716	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448) PG64-22		
16	SPECIAL	827	SY	MILL IN PLACE (EXISTING PAVEMENT)		
<b>DRAINAGE</b>						
17	611	40	LF	12" CONDUIT, TYPE B (SDR 35)		
<b>PAVEMENT MARKINGS</b>						
18	642	1.42	MILE	Center Line, Type 1		
19	642	2.84	MILE	Edge Line, 4 inch, Type 1		
20	642	30	LF	Stop Line		
<b>MISCELLANEOUS</b>						
21	614	1	LS	MAINTAINING TRAFFIC		
22	623	1	LS	CONSTRUCTION LAYOUT STAKES AND SURVEYING		
23	624	1	LS	MOBILIZATION		
					TOTAL BID PRICE =	

ENGINEERS ESTIMATE = \$549,600.00